

Building & Operating A Next-Gen Access Full-Fibre Network

Tom Rigg

COO

t.rigg@b4rn.org.uk

https://www.linkedin.com/in/tsrigg/ https://b4rn.org.uk/



Introduction

Launched in 2011 by local volunteers

Registered as a Community Benefit Society

Our mission remains at the heart of what we do:

To deliver the best internet service in the country to the areas that are hardest to reach, working shoulder to shoulder with, and for, rural communities, to realise the enduring benefits of greater resilience and connectivity.









Technology choices

- Full-Fibre <u>All the way</u>
- Simplistic (by design)
- Built & operated as a single entity
- Future-proof long-term asset
- Proactive approach







ZYXEL

Planning the network

- Create project boundaries with the Community
 - Geography/Geology
 - Existing Infrastructure
 - Local Parish area(s)
 - Best Engineering choices
- Create network plans that allow 100% connectivity
- Liaise with landowners to find suitable paths for installation, make their lives easy, and bring them onboard as part of the build!
- Make provisions to allow for a bottom-up design using local knowledge, not top-down using automation and mapping tools.



Building the network - Core

- 16mm & 7mm Duct Systems
- Vibratory Mole Plough
- Blown Fibre
- 99.9% underground











B4RN[®] Building the network - Customers

- 2 Fibres per property
- Bidirectional single fibre working
- Symmetrical 1Gbps service
- 99.9% underground

Operating the network

• We are our own ISP

B4RN[®]

- AS58273 present in major UK Datacentres
- Ownership & Control from Transit/Peering through to customer CPE
- Built in capacity for current burst events and future expansion
- Controlled (symmetric) paths for all traffic, including sensitive data such as VOIP and Live Video

Exchange I; IPv4 ASN IPv6 IZLeads 56273 91:217.231.48 20017/8.67:e3a1:1 LINK LONI 58273 195.66:226.126 20017/8.42:e3a1:1 LINK LONI 58273 195.66:224:60 20017/8.42:e3a1:1 LINX Sociand 58273 195.66:226 2001.778.43:e3a1:1 LINX Sociand 58273 185.1:195.19 2001.778.34:19 Interconnection Facilities Facility I; Countr Asin City agl_DC5 United Facility MA1 - Manchester. United 58273 Leeds 58273 Edinburgh 58273 Leeds 58273 United 58273 United 58273 Edinburgh Stellium.1 United 54273 Edinburgh Stellium.1 United 54273 Edinburgh Stellium.1 United 54273 Edinburgh Stellium.1 United <th>Speed</th> <th colspan="4">Filter</th>	Speed	Filter				
XLeeds 58273 91.217.231.48 2001.776.67.e3a1:1 LINX.LONI 58273 195.66.24.66 2001.776.41.e3a1:1 LINX.Manchester 58273 195.66.24.66 2001.776.41.e3a1:1 LINX.Scotland 58273 195.66.24.62 2001.778.43.:e3a1:1 NLS.Cotland 58273 195.66.24.62 2001.778.34.:19 NLL.X 56273 185.1.195.19 2001.778.34.:19 Nterconnection Facilities 58273 185.1.195.19 Countr ASN City 301.02.5 United United S273 Leeds 201.778.34.:19 S273 Usingt Countr ASN City 301.02.5 United S273 Leeds United S273 Edinburgh S273 Leeds United S273 Edinburgh S273 S273 Edinburgh United S273 S273 Leeds Edinburgh Manch S273 S273 North North North North S273 Leeds <th></th> <th colspan="3">RS Peer</th>		RS Peer				
LINK_LONI 58273 195.66.226.126 2001.716.4::e3a1:1 LINK_Manchester 58273 195.66.224.60 2001.716.4::e3a1:1 LINX_Scotland 58273 195.66.224.60 2001.716.4::e3a1:1 LINX_Scotland 58273 195.66.224.20 2001.716.4::e3a1:1 LINX_Scotland 58273 185.119 2001.716.3::e3a1:1 NCLUX 58273 Interconnection Facilities Cuty AgLDC5 United 62273 Leeds 52273 Edinburgh Stellium.1 United 58273 Londor	10G	0				
LINX Manchester 58273 195.66.244.60 2001.716.42::e3a1.1 LINX Socialing 58273 195.66.246.26 2001.716.43::e3a1.1 NCL-IX 58273 195.61.91.91 2001.716.34::19 Interconnection Facilities Facility II Country Country ASN Clty agl DC5 United Equinx MA1 - Manchester. United 58273 Leeds 58273 Editionum S2273 United 58273 Editory 58273 Editory 58273 Nanch 58273 Editory S26273 Nanch 58273 Editory S26273 Newca S6273 Newca S6273 Newca S6273 Newca S6273 Londor S6273 Londor	100G	Ø				
LINX Scotland 56273 135 66.246.26 2001/178.43::e3a1.1 NCL-IX 56273 185.1.195.19 2001.778.34::19 Interconnection Facilities Facility L Country ASN City aal LCC5 United Se273 Leeds Se273 United Se273 United Se273 United Se273 United Se273 Edinburgh Se273 United Se273 Edinburgh Se273 Edinburgh Se273 Edinburgh Se273 Edinburgh Se273 Newca Se273 Newca Se273 Newca Se273 Newca Se273 Londor Se273 Londor	100G	\odot				
NCL.IX 58273 185.1.195.19 2001:7/8.34:19 Interconnection Facilities Facility IS Countr AsN ad DC5 United 58273 Leeds Equinx MA1 - Manchester. United 9Usant Editburgh South Gyle United 68273 Edinburgh South Gyle United 68273 Edinburgh South Gyle United 68273 Edinburgh South Gyle United Stellium 1 United Se273 Stellium 1 United Se273 Stellium 1 United Se273 Stellium 1 United Se273 Se273 Londor United	10G	\odot				
Interconnection Facilities Facility II Countin ASN City agLDC5 United Star 23 Leeds Equink MA1 - Manchester, United Williams/Klbum Manch Star 3 Pulsant Edinburgh South Gyle Stellium 1 United Star 3 Telehouse - London (Docklands North) United Star 3	10G	\oslash				
aqLDC5 United 58273 Leeds Equinix MA1 - Manchester, United Williams/Kilburn Manch 58273 United Stellium Stellium Stellium United 58273 Edinburgh Stellium United 58273 Newca Telehouse - London (Docklands North) United 58273 Londor	Filter					
Equinity MA1 - Manchester, United Williams/Kilbum Manch 56273 United Pulsant Edinburgh South Gyle United Stellium.1 United 56273 Edinburgh Stellium.1 United Scart Second Control (Docklands North) United Stellard United Scart Second Control (Docklands North) United	Kingdom					
Pulsant Edinburgh South Gyle United 58273 Edinburgh Stellium 1 United 58273 Newca Telehouse - London (Docklands North) United 58273 Londor	United Kingdom Manchester					
Stellium 1 United 58273 Newca Telehouse - London (Docklands North) United 58273 Londor	United Kingdom Edinburgh					
Telehouse - London (Docklands North) United 58273 Londor	United Kingdom Newcastle					
	Kingdom	_				





29/08/2023

Monitoring & Telemetry

Tota

Devices

- Opensource software & systems
- In-house development team (cannot reiterate how important this is!)
- Proactive monitoring and telemetry management – build in resilience and redundancy







The Copper Switch Off

Why?

• <u>Full-Fibre is the way</u> (has been for a long time) and now that UK industry is fully engaged with FTTP/FTTH the development of copper technologies has drastically decreased.

What?

- Since 2021 Openreach has been ceasing the sale of copper products in areas that can receive 75% Full-Fibre coverage (2,900+ locations Aug 2022)
- In September 2023 Openreach will only provide digital phones
- The target to turn off the Openreach Public Switched Telephone Network (PSTN) and Integrated Services Digital Network (ISDN) is 31st December 2025
- Essential services and areas that cannot receive alternate technologies will remain active (for the time being)

	Full Fibre - Fibre to the Premises					
References:	Generated: Saturday 26th August 2023					
https://www.openreach.com/fibre-broadband/retiring-the-copper-network	UK	England	Northern Ireland	Scotland	Wales	
https://labs.thinkbroadband.com/local/uk	55.3%	54.6%	92.9%	50.0%	53.9%	

The Copper Switch Off

Impact?

- Telephony traffic paths are changing
- Equipment requirements are different
- The industry as a whole, including network operators, equipment manufacturers, software developers, technical specification writers, you name it, need to embrace this change as the entire world moves to Full Fibre

Abbeystead Hydro - 2019

• What goes unseen? Care & welfare, burglar, building lift alarm systems, equipment/plant/machinery monitoring and control (We have local Community Hydro power plants on-net with Full Fibre)





References:

https://haltonlunehydro.org/

https://www.ellergreen.com/hydro/portfolio-item/abbeystead/

Building & Operating A Next-Gen Access Full-Fibre Network 10

29/08/2023

HALO Project

- 654km of Dark Fibre lit with 400Gb of capacity
- Two long distance 100Gb Wavelengths
- Resilient & diverse regional network for all distribution nodes & B2B customers
- Automatic failover with enough capacity to send all traffic either way
- Ability to gracefully shutdown one leg for maintenance and repair

Dark Fibre: **Zayo**^{*} Fibre Drivers: **Smortoptics** Routers & Switches: JUNIPEC



HALO Project

- Clean + Test, clean again, test again, clean some more... You get the point
- Plan the deployment, stress test the plan, update the plan, be prepared for the unknown
- Manage teething issues as they are presented to you in a proactive and responsive way
- Build systems in a test environment tackling the configuration challenges before equipment deployment
- Audit everything track the changes, track the equipment, label it all physically and logically



HALO Project

- Platforms & their rotation:
 - To retire: MX80, MX240, MX480, EX4550
 - To retain: QFX5100, QFX5110, QFX5120
 - To install: MX304, ACX7100-32C, ACX7100-48L
- Border network operation
 - healthy IP Transit/Peering/PNI configuration
- P/PE/CE network operation
 - Interlink & meshing over controlled paths
 - Ability to handle link failures with no customer impact
- Build in the resilience from day one!









400Gb Low Latency

- IP over DWDM utilising OpenZR 400G 16QAM CFEC
- Direct relationship between physical fibre, optical drivers, and networking equipment
- Understand the fibre G.652/G.655/G.657.A1
- 10G 40ch Mux/Demux vs 400G 40ch Mux/Demux

smartoptics

												_
			-									
smortoptics	921 922 10 10 10 10	925 928	929 930	933 954 977 974	937 938		941 942	945 945 1945 1945	949 950 1000000	953 954 ECHIES ECHIES	957 958	
Par Sts	1111111 1111111 1111111 1111111 1111111 1111111 1111111 1111111 1111111 1111111 1111111 1111111 1111111 1111111 1111111 1111111 1111111 1111111 11111111 11111111 111111111 1111111111	Homese Homese 927 928	1000000 Bitmana 931 932		EXAMPLE 1	32		10110100000000000000000000000000000000	HOME BOARD		1000 000	3333333













Questions?



Tom Rigg COO t.rigg@b4rn.org.uk https://www.linkedin.com/in/tsrigg/ https://b4rn.org.uk/



